	Specs As of 5/6/2016	I
FLOOR	Specs As of \$ \$701\$	Express Modular
JOIST:		Express inodular
SIZE	First Floor 2" x 10" #2 / Open Joist Second Floor	X
SPACING	16" O.C	X
INSULATION	R-30 Floor Insulation in the area of the second floor above the porch	X
	on the Models A-2, B-1, B-2 only. Insulation is required around rim	
	joist in second floor of all units	
DECKING	5/8" 4x8 T/G OSB	X
RIM JOIST	Double 2X10	X
MARRIAGE BEAM	Double 2X10	Х
SOLID BLOCKING	2x4 Bridging	Х
JOIST HANGER	Ledger Strip	X
CARPET:		
STD TYPE	25 Oz. Residential Carpet	Х
STD AREAS	Master Bedroom / Stairs	Х
CARPET PAD:	5 lb. Pad	X
LINO:	J ID. 1 ad	X
	IZOLOGI DETECTION DE LO LOGICO DE LO LOGICO DE LA CONTRA DE LOGICO DE LO CONTRA DEL LO CONTRA DE	V
STD AREAS	Kitchen, Utility, Baths, Hall, Bedrooms, LR, and Foyer	X
<u>WALLS</u>		Express Modular
EXTERIOR:		
STUDS:		
SIZE	2x6 #2	Х
HEIGHT	96"	X
SPACING	16" O.C.	X
TOP PLATE	Double 2x6	X
BOTTOM PLATE	Single 2x6	X
SHEATHING	Full 7/16" OSB Exterior Wrap	X
HOUSE WRAP	House Wrap per State Code Application	X
EXTERIOR DRYWALL B-1	5/8" Type " X" Exterior Grade Drywall on One Wall on Model B-1	Optioned In
	Location to be determined by the Architect and Marked per Print	
INTERIOR DRYWALL	5/8" Type " X " Drywall	Х
PAINT	1 Coat of Tinted PrimerColor Seed Pearl	Х
INSULATION	R-19 Fiberglass Batts	X
INTERIOR:	10 Tibergiass Batts	, A
PARTITIONS:	0/4.0/ 10 1 0 5 #	· · · · · · · · · · · · · · · · · · ·
STUDS	2X4 Stud Grade Or Better	X
STUD SPACING	16" O.C.	X
TOP/BOTTOM PLATES	Single 2X4	X
PLUMBING		
STUDS	2X6 or 2X4	Х
STUD SPACING	16" O.C.	Х
TOD/DOTTOM BLATEO		.,
TOP/BOTTOM PLATES	Single 2X6 or 2X4	X
DRYWALL	5/8" Type " X " Drywall	X
PAINT	1 Coat of Tinted PrimerColor Seed Pearl	X
MARRIAGE		
STUDS	2X6	Х
STUD SPACING	16" O.C.	X
DRYWALL	5/8" Type " X " Drywall	X
PAINT	1 Coat of Tinted PrimerColor Seed Pearl	X
TOP PLATE	Double 2X6	X
BOTTOM PLATE	Single 2X6	X
SHEATHING	Full 7/16" OSB Exterior Wrap	X
INSULATION	R-19 Fiberglass Batts	Х
ROOF & CEILING		Express Modular
ROOF PITCH	all units 5/12	X
SPACING	24" O.C 30# L.L.	Х
EAVES	12"	X
CEILING	5/8" Type "X" Sheetrock - Stomp Finish	X
ROOF SHEATHING	7/16" OSB	X
NOOF SHEATHING		
	#15 Paper over entire roof.	X
ROOF UNDERLAYMENT	D. I.	
ROOF UNDERLAYMENT	Provide Ice and Water Sheild	
ROOF UNDERLAYMENT VENTILATION	Passive Vents installed in the Hat Sections per Side	X
ROOF UNDERLAYMENT	Passive Vents installed in the Hat Sections per Side R-40 Blown Cellulose	X
ROOF UNDERLAYMENT VENTILATION	Passive Vents installed in the Hat Sections per Side	
ROOF UNDERLAYMENT VENTILATION INSULATION	Passive Vents installed in the Hat Sections per Side R-40 Blown Cellulose	X
ROOF UNDERLAYMENT  VENTILATION INSULATION BAFFLES	Passive Vents installed in the Hat Sections per Side R-40 Blown Cellulose At Eaves	X X

SIDING		Express Modular
TYPE	Traditional Double 4" Vinyl Siding. Siding will be standard gage .042	Х
FASCIA TRIM	White	X
SOFFIT	White Fully Vented Vinyl	X
SHINGLES	Dimensional - 30 Yr.	X
SHUTTERS	Lineal Treatment ( Similar to Crane Lineal )	Х
ATTIC VENTILATION	Passive Vents installed in the Hat Sections per Side	Х
TRIM	Lineal Treatment ( Similar to Crane Lineal )	X
	All J-Channel to match Siding	X
<u>WINDOWS</u>		Express Modular
GRID	6 over 6 Grids	Х
TYPE	Vinyl Double Hung, Low "E", with Grids White (U Factor .35 or below)	X
SIZE	See Print	Х
INSTALLATION	Forti-Flashing at All Exterior Window and Door Penetrations	X
DRAPERY	None	Х
BLINDS	2" PVC Mini-Blind T/O	Х
TUB DRAPE	None	Х
<u>DOORS</u>		Express Modular
INTERIOR:		
STYLE	36" / 32"/ 24" White 6 Panel H/C	Х
JAMBS	Home Town Ash Pine Jambs	Х
HARDWARE	Nickel Lever Knobs/ 3 Mortised Hinges	Х
EXTERIOR:		
FRONT	Georgia Pacific Steel Frame w/ 6 Panel Vinyl Door, ADA Sill, Door Sweep	Х
	and 1Small Window in each of the Top 2 Top Panels. Nickle Kick Plate	
	Peep Hole at 5'	
LOCKSET	ND53PD Lever Lock Grade 1,B660P Deadbolt Grade 1,Drip Cap	Х
REAR	Georgia Pacific Steel Frame w/ 6 Panel Steel Door, ADA Sill, Door Sweep	Х
	20 minute Rating, Peep Hole ar 5'	
LOCKSET	C-11 Arrow Lever Lock Grade 2,E-61 Arrow Deadbolt Grade 2,Drip Cap	Х
PLUMBING FIXTURES		Express Modular
NOTE:	Anti Scald devices per code	· X
	All Bath Tub / Showers & Showers shall have offset controls	Х
NOTE:	All Faucets to be Moen Chrome	Х
BATH 1 :		
TUB SHOWER	White 60" 1-Pc. Fiberglass Tub / Shower	Х
NOTE:	Must have straight shower rod and curtain for all showers	
COMMODE	Elongated	Х
LAVATORY	White China	Х
LAVATORY FAUCETS	Metal -Single Lever- Brushed Nickle	Х
TUB/SHOWER CONTROL		Х

TOWEL BAR	Brushed Nickle 1 each restroom	Х
PAPER HOLDER	Brushed Nickle 1 each restroom  Brushed Nickle 1 each restroom	X
BATH 2 :	Diustieu filickie i each restroom	^
TUB	White 60" 1-Pc. Fiberglass Tub Shower VBP	X
NOTE:	Must have straight shower rod and curtain for all showers	^
COMMODE	Elongated	X
LAVATORY	White China	X
LAVATORY FAUCETS	Metal -Single Lever- Brushed Nickle	X
	Metal Brushed Nickle	X
BATH VENTS	Lighted Fan 75 CFM	X
BATH VENTS	Eave Vent Top Floor	X
	Side Discharge Bottom Floor	X
KITCHEN:	Side Discharge Bollom Floor	
KITCHEN: KITCHEN SINK	7 1/2" Stainless Steel	X
KITCHEN SINK KITCHEN FAUCET		X
	Metal - Single Lever Pullout Sprayer	
ICEMAKER	All First area	X
WATER SHUTOFFS	All Fixtures	X
WATERLINES	PEX	X
DRAIN/VENT LINES	Schedule 40 PVC	X
PLUMB FOR WASHER	Per Plan	Х
FROST FREE FAUCETS	1 Per Print w/ Shutoff - Side of Unit See Print	
ELECTRICAL		Express Modular
SERVICE	200 AMP Panel (Each Living Unit)	X
Mounting Location	TBD	
WIRING	12-2 Copper Minimum T/O	Х
	Electrical Outlets and Cable devices set to a minimum height of 18" AFF	Х
SMOKE /CO2 DETECTOR	All Bedrooms, LR and 1 Ship Loose for Basement onsite Installation	Х
CABLE/PHONE/DATA	All Bedrooms & LR (Location to be determined by GC)	X
GFI RECEPTS	Kitchen, Baths, Exterior ( 2 per unit )	Х
INTERIOR LIGHTS		Express Modular
BEDROOMS	11" BF-102024-401 W/GLOBE BG-190082-40	Х
	11" BF-102024-401 W/GLOBE BG-190082-40	X
OPEN LOFT AREA	11" BF-102024-401 W/GLOBE BG-190082-40	Х
ATTIC	4" Fitter BF-100202-008 W/GLOBE BG-190020-008	Х
BATHS	LF-103316-250/LF-103316-401 18" 2 BULB STRIP	Х
KITCHEN LIGHTS	11" BF-102024-401 W/GLOBE BG-190082-40	X
LIGHT BULBS	Non Provided	X
EXTERIOR LIGHTS		Express Modular
FRONT DOOR	Torch "Black"	X

APPLIANCES		Express Modular
	Whirlpool Appliance Brands may Vary	
RANGE	30" Free-Standing Electric Std Clean Elec - FFE3011LWJBS27DMWW -	X
MICROWAVE	Above The Range Microwave Model	X
REFRIGERATOR	18 Cu. Ft.	X
WATER HEATER	None Provided	
DISHWASHER		X
GARBAGE DISPOSAL	Badger 1/2 HP	X
WASHER	None Provided	
DRYER	None Provided	
MOULDINGS	Testion Tovidou	Express Modular
DOORS:	Hometown Ash	
DOOR CASING	2 1/4" Trim Color to Match Cabinet (Domestic)	Х
DOOR STOP	Trim Color to Match Cabinet (Domestic)	X
DOOR JAMB	Home Town Ash Wrapped Jambs	X
WINDOW:	Home Town Ash Wrapped Jamus	
	2 1/4" Trim Color to Match Cabinet (Domestic)	X
WINDOW LAMP		
WINDOW JAMB	3/8" Particle paper Color to Match	X
BASE	Divid	X
TUB MOLDING	Plastic	
STAIRWELL SKIRT BOARD	Pine Board Stained to Cabinet color	X
<u>CABINETS</u>		Express Modular
NOTE:	Cabinets Spec Color is Hometown Ash Finish.	X
KITCHEN / UTILITY		
BASE & OVERHEAD CABINETS:	Overheads are NON-Staggered	
DOORS	Flat Panel Oak	X
STILES & RAILS	Solid Hardwood	Х
SIDE PANELS	Exposed: 1/2" Laminated	Х
BACK PANELS	Exposed: 1/2" Laminated	Х
OVERHEAD SHELF	Adjustable center shelf	Х
BASE SHELF	1/2" Fixed	Х
UTILITY	Wire Shelf	Х
DRAWERS	Above Doors (except sink) w/Deluxe Roller Guides - Extendable	X
HARDWARE	Hidden Hinges	X
PULLS	Nickel	X
COUNTERTOPS	High Pressure Laminate w/Self Edge	X
BACKSPLASH	6" Ceramic	X
KITCHEN CABINET TRIM	O GOIGITHO .	
TOTIEN GABINET TRIVI	2-1/2" Ash Cove Top Of Cabinets	X
	Lip Moulding Bottom Moulding	X
BATH CABINETS:	Elp Woodialing - Bottoff Woodialing	
DOORS	Flat Panel Color to Match Cabinets Home Town Ash	X
PULLS	Nickel	X
COUNTERTOPS		
	High Pressure Laminate w/Self Edge	X
BACKSPLASH	6" Ceramic	X
MIRRORS	Polished Edge (Size TBD ) i	X
CLOSETS	W. O. K	Express Modular
SHELVING	Wire Shelf	X

<u>HEATING</u>		Express Modular
REGISTERS	Drop In Registers w/6" Round Boots	Х
	Toekick Registers Kitchen & Baths	X
	Cold Air Returns in second floor ceiling per print	Х
	Send 18" Return air hose and collection box for ceiling	Х
FURNACE w/DUCT WORK	None ProvidedWe will provide the wall stacks in the first floor	Х
	and duct work, hoses and registers for the second floor	
	First floor registers boots and registers only installed at the plant.	
THERMOSTAT WIRE	18 gauge 8 wire installed at 48" AFF dropped thru floor	X
	for onsite connection to onsite installed furnace	
NOTE:	No Thermostat Provided	Х
NOTE:	All materials will be subject to availability. Substitutions will be	Х
	of equal or better quality and specifications.	
NDER PORCH MATERIAL	ProvidD Onsite By Others	Optional